



#### Leuven case study

#### International workshop & project meeting Leuven, 16-17 April 2012

Johan Van Assel (Aquafin) Laurens Cas Decloedt, Patrick Willems (KU Leuven)



# National partners involved



Aquafin

- WP1
  - Radar
    - Owned by Aquafin
    - Operated jointly by Aquafin and KU Leuven
    - Technical Service and Maintenance : DHI (DK)
  - Raingauges
    - Existing raingauge netwerk owned and operated by Aquafin
    - Additional raingauges + new telemetry system owned and operated by Aquafin
- WP2
  - All radar and raingauge data analysis and calibration by KU Leuven
  - All rainfall forecast calculations by KU Leuven
  - Data collection and transformation to model input by Aquafin



# National partners involved (2)



- WP3
  - Flood and forecast modelling by Aquafin
  - Provision of data for model update and validation :
    - Municipalities of Leuven and Herent (Observers)
  - Provision of realtime and forecast watercourse data (still to be discussed)
    - Flemish Environmental Agency (VMM) (Observer)
- WP4
  - Flood forecast and management system setup by Aquafin
  - Advise and support by National Observers Group





## LAWR City Radar

- Marine X band technology (type Furuno) operating at 9.41GHz with a wavelength of 3.2cm, pulse length of 0.8µs and peak output of 4kW
- Logarithmic receiver with a 0.4m radome antenna
- Vertical opening angle of 20 (lower half is cut of by pit wall) horizontal opening angle of 4 (only 1 elevation)
- Range of 15km for qualitative precipitation estimation (QPE) and 30km for forecasting rainfall
- Spatial resolution of 250x250m (range: 30km) up to 50x50m (range: 7.5km)
- Temporal resolution of 1 or 5 minutes (1 minute is used) with 450 samples per rotation and 24 rpm



## LAWR City Radar (2)



#### Location : Province building

- Chosen after initial clutter tests 2007
- Advantages :
  - highest building in surroundings
  - power, broadband available,
  - roof acts as natural clutter fence
- Disadvantages :
  - blind sectors due to
    - proximity of airport (obligatory)
    - maintenance crane on roof (de facto)
  - access on request








#### LAWR City Radar (3)



Blinding and natural clutter fence on rooftop



#### Comparison of clutter at various candidate locations








## Rain gauge network

- Aquafin rain gauge network
  - Currently 4 gauges; to be extended to 8 shortly
  - Realtime data retrieval to be installed shortly
  - TBR 0.2 mm 2 min interval
  - Dynamic calibration carried out by KU Leuven (2007) (correction for tipping losses)
  - Wind effect corrections to be investigated
- RMI rain gauge network
  - 3 gauges within appr. 10 km distance
  - Daily totals (only for historic data -no subscription)
  - 0.1 mm resolution
  - Used for historic validation and wind effect calibration
- VMM rain gauge network
  - 3 gauges linked to CSO Monitoring scheme
  - Monthly data exchange
  - TBR 0.2 mm 10 min interval
- Other
  - used in river flood forecast systems
  - Availability of data to be investigated





#### Rain gauge network








#### Other radars

- RMI
  - Existing C-band radars in Zaventem (owned by Belgocontrol) and Wideumont
  - Startup (test) of new dual pol C-band radar in Jabbeke
- VMM
  - New dual pol C-band radar planned in Houthalen (timing : end 2013?)
  - Subscription to realtime Belgian-Dutch-French composite data





#### Other radars





#### Radar calibration activities



- Extra parameters influencing the radar-rain gauge relationship investigated:
  - Seasonal variance
  - Convective or stratiform nature Temperature
  - Mean rainfall intensity

- Wind speed & direction
- Size of precipitating system
- Extra algorithms implemented and adapted to obtain extra parameters
  - Convective stratiform separation algorithm (Steiner et al. 1995)
  - Cloud movement and direction algorithm
- Significant correlations for some parameters


# 



#### Influential parameters



- Season:
  - Spring higher, summer and autumn similar and winter lower
  - Supports Convective / Stratiform separation algorithm
- Direction:  $\bullet$ 
  - Nearly no East
  - West & North similar
  - South higher
- Velocities within direction:
  - West: increasing relation found




Raingain Project meeting 17/04/2012 - Aquafin & KU Leuven



#### Influential parameters



- Area:
  - No increasing relation, however, for relative radar filling levels within 40-50%, a higher relation is eminent
  - Supports Convective / Stratiform separation algorithm
- Temperature:
  - T <10° lower,
  - 10° T<20° higher
  - $-T > 20^{\circ}$  mean
  - Supports Conv./Strat.
- Intensities:
  - Increasing relation, \_ but not super clear







### Sewer system

- Drainage area Leuven
  - Central WWTP : approx. 120000-150000 PE
  - Approx. 120 km<sup>2</sup>
  - Spread over 6 municipalities
    - Leuven, Herent, Bertem, Lubbeek, Holsbeek, Oud-Heverlee
  - Characteristics :
    - Combination of moderately steep parts and flat valleys
    - Storage trunk sewers, as well as pumps+rising mains
    - Mostly combined; separate in new developments or recent project areas






## Drainage area

- 2 main sub-areas : North (approx. 30000PE) South (approx. 120000 PE)
- North : all major drainage projects completed
  - Case study for first phase
- South : some major projects still planned/under construction
  - (largely) to be included in second phase case study











## Monitoring campaigns

#### Northern part


- Monitoring at certain locations since 2005
  - Flow, depth, CSO spills, pump operation
- Most data not available in realtime
  - Used for historic model verification
- Southern part
  - Very little monitoring at present
  - RTC pilot implementation underway in Kessel-Lo area (close to WWTP)



 $\bigstar$  Flow and depth monitoring

#### Monitoring in northern part










## Sewer modelling

- Existing model
  - Detailed models available for almost all of the area (InfoWorks CS)
  - Not all areas equally up-to-date
    - Recent local sewer projects to be obtained from various municipalities
    - Contributing areas to be checked
  - Model verification for some areas (especially in southern part) almost 10 years old





### Existing model





0.40

0.00

#### Recent model verification (raingauges only)




#### Observed / Predicted Plot Produced by user1774 (21/02/2012 14:51:23) Page 2 of 3 Flow Survey: >week 40-43 (okt 2011)>Metingen SFC>week 40 SFC (8/07/2009 10:31:50) Sim: >Networken en simulaties>N2 - zonder sed\_M9 ruwe neerslag>N2 - week 40>4 pluvio's (1409-3110) (16/12/2011 18:11:12) Sim: >Networken en simulaties>nieuw DWA-profiel>week 40>4 pluvio's (1409-3110) (21/02/2012 14:47:53) Graph Template: >Networken en simulaties>Graph Template Group>Graph Template SPC 2011 - aangepast voor M9 (21/11/2011 12:06:16) Flow Survey Location (Obs.) M8, Model Location (Pred.) D/S 131009.1 Depth (m) 0.250 0.200 0.150 0.100 0.050 0.000 Flow (m3/s) 0.08 7 0.06 0.04 0.02 -0.00 -0.02 Velocity (m/s) 0.80



## **Recent model verification**



#### (raingauges only)






#### Comparison radar vs. raingauges input



#### Hooate M5 Pluvio model 0.8 Radar model Metina 0.7 0.6 0.5 Hoogte [m] 0.3 0.2 0.1 10/02/2011 11/02/2011 11/02/2011 12/02/2011 12/02/2011 13/02/2011 Tijd






#### Comparison radar vs. raingauges input



# Raingain Project meeting 17/04/2012 - Aquafin & KU Leuven





## Main issues in the



#### area

- List of problem areas (flooding) discussed with Herent and Leuven
  - Some typical urban floods
    - Due to sewer undercapacity, interaction with (small) receiving watercourses
  - Some locations due to pervious area runoff
    - Overland runoff from agricultural areas etc. drains to sewer
    - Highly dependent on seasonal variations (soil wetness, ...)
  - Sewer / watercourse interaction important to take into account
    - Obtain and integrate real time predictions from VMM ?
- CSO spill reduction
  - Second priority after flood prevention
  - To be optimised by using RTC
- PS optimisation
  - Make sure all pumping stations are conform with minimal operational performance requirements



# Planned activities for next 6 months

שער

- WP1
  - Install new raingauges and telemetry system
  - Write and test scripts for realtime radar data retrieval and processing
  - Create first prototype of radar web viewer (limited access)
- WP2
  - Improve radar calibration
  - Additional raingauge calibration
- WP3
  - Continue detailed validation of northern part based on permanent monitoring
  - Extend (parts of) existing model with 2D data (DTM, detailed background map)
  - Try out various approaches of flood modelling
  - First trials with FloodWorks (forecast model)
- WP4
  - Follow up actions from first NOG meeting